

## Installation Service Technician Work

### Work allowed = REPAIR or REPLACE

1. STP / LLD
2. Interstitial sensors
3. ATG probe
4. High level alarm
5. Drop tube / shutoff valves
6. Monitoring system (troubleshooting alarms, replacing existing CSLD chips)
7. Shear valves
8. Containment repairs (where concrete is not broken)
9. Transition piping (where concrete is not broken)

### Work NOT allowed:

1. Installation of equipment not previously onsite (including equipment above)
2. Any work where concrete is broken
3. Stage 2 decommissioning
4. Re-hooking up piping and certifying OOS tanks go to back into use
5. Monitoring panel installation or system upgrade (examples: software upgrade or adding CSLD; replacement of CPU/motherboard)
6. Internal lining – inspection or repair
7. Anything CP related
8. Any work which requires a sub-mod permit
9. Any work which requires an installation-entire for any portion of the job.